

PROJECT: Lovington Fire Station # 2
WDG PROJECT NO: 445-02
DATE: September 25, 2018

ADDENDUM NO. 5

NOTICE TO PROPOSERS: This Addendum forms a part of the Contract Documents and modifies the original Specifications and Drawings for Lovington Fire Station # 2, dated June 30, 2017 (drawings) and July 5th, 2018 (specifications.)

Acknowledge receipt of this Addendum in the space provided in the Proposal Form. Failure to do so may disqualify the Bidder.



David W. Clarke

September 25, 2018
Date



CLARIFICATION:

1. Detail 3 Sheet S101 doesn't match Note #5 under Foundations on Sheet S100 – Please clarify?
Detail 3 on sheet should match Note #5. Note # 5 is correct.
2. Section 095123 Under 1.3 Line C – is the contractor or sub responsible to hire an engineer for design calculations for seismic restraints including analysis data?
For seismic load requirements refer to sheet S100. Metal suspension system for Acoustical ceiling shall comply with ASTM C 636. Remove note: Line C, under 1.3 of Section 095123
3. What is block color for exterior site walls?
Provide standard grey block.
4. What is reinforcing requirements for site walls?
Provide #5 bar reinforcing bars for site walls at 32" o.c. and typical truss type reinforcing 16" o.c.

END OF ADDENDUM NO. 5